

A primer on how to take overhead electric and phone/internet cables underground in
Interlaken Town:

Contact Heber Light and Power and CenturyLink (see contacts below) to walk the site with you. Each company requires some type of staking sheet (survey) for them to start the process and invoice you for their services. For reference at 338 Luzern Rd job (completed in 2023, ~300' of line buried) the CenturyLink Special Construction Contract charge was \$13,610 for CenturyLink to place the new cable in the conduit and remove the existing cable. Heber Light and Power fee to do the same was \$14,215.

The property owner is required to bury the conduits at the property at the owner's expense: CenturyLink minimum requirement is 2" conduit from pole to pole. HL & P requires a 3' separation between the electric and cable conduits, the electric conduit must be buried 4' below grade, shaded with sand above and below with caution electric service tape laid ~18" above the conduit that will carry the electric lines (for H&LP Standards go to: [HLP Standards](#)). Once the conduits are buried and risers installed HL&P and CenturyLink will place their lines in the conduits and remove the existing aerial lines.

The key contacts for CenturyLink and Heber Light and Power:

Brandon Michaelis
Engineering Manager
Niels Fugal Sons Company, LLC
Mobile: 801-750-3561
Email: brandon.michaelis@fugal.com

Riley Wright (Onsite inspections)
Project Manager
Heber Light and Power
Office: 435-657-6423
Mobile: 435-671-1318
Email: rwright@heberpower.com

Cathie Bethers (In office Contact)
Project Coordinator
Heber Light & Power
O: (435) 657-6424
Email: cbethers@heberpower.com